



<b>Project Name</b>	<b>Project Location</b>	
Serramonte Vista Commercial Site	Daly City, CA	5/11/2009
<b>DESIGN DEVELOPMENT ESTIMATE</b>		
DD Drawings dated 4-28-09 & BKF Drawings dated 3/23/09		
<b>ESTIMATE SUMMARY: Based on Type V 1 hr - Wood Framed Structure</b>		

<b>Construction Cost</b>			
	<i>Parking</i>	<i>Residential</i>	<i>TOTALS</i>
	385 stalls	70 units	
<b>UNIT GSF</b>			
TOTAL GROSS SQUARE FT.	91780	88900	180680
TOTAL NET SQUARE FT		65750	65750
TOTAL SHELL COSTS	\$3,636,817	\$11,167,606	\$14,804,423
TOTAL FINISHES COSTS		\$1,964,277	\$1,964,277
<b>DIRECT CONSTRUCTION COST</b>	<b>\$3,636,817</b>	<b>\$13,131,884</b>	<b>\$16,768,701</b>

DIRECT CONSTRUCTION COST PER GSF	\$40	\$148	\$93
----------------------------------	------	-------	------

DIRECT CONSTRUCTION COST PER NSF		\$200	\$255
----------------------------------	--	-------	-------

DIRECT CONST. COST PER UNIT	\$9,446	\$187,598	\$239,553
-----------------------------	---------	-----------	-----------

DIRECT CONSTRUCTION COST	\$3,636,817	\$13,131,884	\$16,768,701
CONSTRUCTION CONTINGENCY	\$90,920	\$328,297	\$419,218
SUB-TOTAL	\$3,727,738	\$13,460,181	\$17,187,918
GENERAL CONDITIONS	\$111,832	\$410,536	\$522,368
INSURANCE	\$28,115	\$101,568	\$129,683
CONSTRUCTION FEE	\$105,588	\$381,445	\$487,033
<b>TOTAL CONSTRUCTION COST</b>	<b>\$3,973,273</b>	<b>\$14,353,729</b>	<b>\$18,327,002</b>

TOTAL COST PER GSF	\$43	\$161	\$101
--------------------	------	-------	-------

TOTAL COST PER NSF		\$218	\$279
--------------------	--	-------	-------

AVERAGE COST PER UNIT	\$10,320	\$205,053	\$261,814
-----------------------	----------	-----------	-----------

**Notes:**

- 1 Includes design of concrete & MEP
- 2 Excludes all other design and soft cost
- 3 Excludes permit costs
- 4 All prices are current prevailing wage market prices.  
No allowance for escalation is included.
- 5 Excludes any costs for payment and performance bonds

## Serramonte Vista Commercial Site

### Square Foot Summary per Unit Type

	Bedroom/Bath	No.	SF	Total SF
1 Bedroom	1/1	35	800	28000.00
2 Bedroom	2/2	31	1050	32550.00
3 Bedroom	3/2	4	1300	5200.00
<b>Totals</b>		<b>70</b>	<b>939.29</b>	<b>65750.00</b>
Building GSF				88900.00
Net Residential Area				65750.00
% efficiency				74%
				23150.00

Division / Description	Total	Per Unit	Per GSF	Per NSF
Division 2 - Demolition	\$53,500.00	\$764.29	\$0.60	\$0.81
Division 2 - Sitework	\$4,151,426.79	\$59,306.10	\$46.70	\$63.14
Division 2 - Landscape	\$100,000.00	\$1,428.57	\$1.12	\$1.52
Division 2 - Site Furnishings	\$25,000.00	\$357.14	\$0.28	\$0.38
Division 2 - Monument Allowance	\$7,500.00	\$107.14	\$0.08	\$0.11
Division 3 - Concrete	\$2,455,452.00	\$35,077.89	\$27.62	\$37.35
Division 4 - CMU & Masonry	\$30,580.00	\$436.86	\$0.34	\$0.47
Division 5 - Structural Steel	\$90,000.00	\$1,285.71	\$1.01	\$1.37
Division 5 - Misc. Metals	\$140,900.00	\$2,012.86	\$1.58	\$2.14
Division 6 - Rough Carpentry	\$2,298,618.00	\$32,837.40	\$25.86	\$34.96
Division 6 - Finish Carpentry	\$127,141.30	\$1,816.30	\$1.43	\$1.93
Division 6 - Cabinets	\$0.00	\$0.00	\$0.00	\$0.00
Division 6 - Countertops	\$0.00	\$0.00	\$0.00	\$0.00
Division 7 - Waterproofing	\$83,212.50	\$1,188.75	\$0.94	\$1.27
Division 7 - Insulation	\$108,580.26	\$1,551.15	\$1.22	\$1.65
Division 7 - Spray Insul	\$66,675.00	\$952.50	\$0.75	\$1.01
Division 7 - Fireproofing	\$46,500.00	\$664.29	\$0.52	\$0.71
Division 7 - Roofing	\$133,350.00	\$1,905.00	\$1.50	\$2.03
Division 7 - Caulking	\$18,648.00	\$266.40	\$0.21	\$0.28
Division 7 - Flashing	\$153,980.00	\$2,199.71	\$1.73	\$2.34
Division 8 - Windows	\$197,265.60	\$2,818.08	\$2.22	\$3.00
Division 8 - Doors	\$220,600.00	\$3,151.43	\$2.48	\$3.36
Division 8 - OH Doors	\$25,000.00	\$357.14	\$0.28	\$0.38
Division 8 - Storefront	\$0.00	\$0.00	\$0.00	\$0.00
Division 8 - Mirrors / Shower Doors	\$0.00	\$0.00	\$0.00	\$0.00
Division 9 - Metal Frame	\$0.00	\$0.00	\$0.00	\$0.00
Division 9 - Drywall	\$986,446.40	\$14,092.09	\$11.10	\$15.00
Division 9 - Plaster	\$0.00	\$0.00	\$0.00	\$0.00
Division 9 - Scaffold	\$74,592.00	\$1,065.60	\$0.84	\$1.13
Division 9 - Tile	\$5,000.00	\$71.43	\$0.06	\$0.08
Division 9 - Wood Fl.	\$0.00	\$0.00	\$0.00	\$0.00
Division 9 - Resilient	\$67,175.48	\$959.65	\$0.76	\$1.02
Division 9 - Carpet	\$158,877.17	\$2,269.67	\$1.79	\$2.42
Division 9 - Painting	\$311,710.19	\$4,453.00	\$3.51	\$4.74
Division 10 - Bath Acc.	\$15,750.00	\$225.00	\$0.18	\$0.24
Division 10 - Striping/Signage	\$7,500.00	\$107.14	\$0.08	\$0.11
Division 10 - Trash Chutes	\$20,000.00	\$285.71	\$0.22	\$0.30
Division 10 - Mailboxes	\$4,500.00	\$64.29	\$0.05	\$0.07
Division 10 - Common Bath Allowance	\$0.00	\$0.00	\$0.00	\$0.00
Division 10 - Bike Racks	\$0.00	\$0.00	\$0.00	\$0.00
Division 10 - Awnings	\$0.00	\$0.00	\$0.00	\$0.00
Division 11 - Appliances	\$180,561.50	\$2,579.45	\$2.03	\$2.75
Division 12 - Fireplaces	\$0.00	\$0.00	\$0.00	\$0.00
Division 12 - Blinds	\$22,377.60	\$319.68	\$0.25	\$0.34
Division 14 - Elevators	\$155,000.00	\$2,214.29	\$1.74	\$2.36
Division 15 - Fire Prot.	\$412,042.00	\$5,886.31	\$4.63	\$6.27
Division 15 - Plumbing	\$1,634,000.00	\$23,342.86	\$18.38	\$24.85
Division 15 - HVAC	\$762,167.00	\$10,888.10	\$8.57	\$11.59
Division 16 - Electrical	\$986,778.00	\$14,096.83	\$11.10	\$15.01
Division 16 - Tele/Data	\$108,487.50	\$1,549.82	\$1.22	\$1.65
Division 16 - Security	\$30,000.00	\$428.57	\$0.34	\$0.46

## Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA		UOM TOTAL	\$/UNIT	TOTAL \$
				AREA	QTY			
<b>02900 DIVISION 2 EARTH WORK</b>								
On-Site Demolition	1	ls		SHELL	1	1	\$38,500.00	\$38,500.00
Off-Site Demolition	1	ls		SHELL	1	1	\$15,000.00	\$15,000.00
Fine Grading and Backfill Items	61000	sf		SHELL	1	61000	\$2.50	\$152,500.00
Mass Excavation	15756	cy		SHELL	1	15756	\$22.50	\$354,510.00
Property Line Chain Link Fencing	534	lf		SHELL	1	534	\$75.00	\$40,050.00
Shotcrete Soil Nail Walls	19350	sf		SHELL	1	19350	\$64.00	\$1,238,400.00
Shoring at Structure	16722	sf		SHELL	1	16722	\$65.00	\$1,086,930.00
Off-Site Concrete	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Concrete Curb	470	lf		SHELL	1	470	\$20.00	\$9,400.00
SWPPP - Allowance	1	ls		SHELL	1	1	\$25,000.00	\$25,000.00
Street sidewalk replacement - Allow	1500	sf		SHELL	1	1500	\$10.00	\$15,000.00
Curb & gutter	474	lf		SHELL	1	474	\$35.00	\$16,597.35
Keystone Retaining Walls	6807	sf		SHELL	1	6807	\$40.00	\$272,277.44
Off-Site and Site Concrete Prep and Base	1	ls		SHELL	1	1	\$15,000.00	\$15,000.00
Landscape at street and podium - Allow	1	ls		SHELL	1	1	\$100,000.00	\$100,000.00
Site Furnishings - Allow	1	ls		SHELL	1	1	\$25,000.00	\$25,000.00
Monument sign Allowance	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Off-Site Traffic Signaling	0	ls		SHELL	1	0	\$265,000.00	\$0.00
Sanitary Sewer	150	lf		SHELL	1	150	\$220.00	\$33,000.00
Storm Drain	250	lf		SHELL	1	250	\$220.00	\$55,000.00
Water Service line offsite	0	lf		SHELL	1	0	\$200.00	\$0.00
Domestic Water Service line	150	lf		SHELL	1	150	\$200.00	\$30,000.00
Fire Water Service line	75	lf		SHELL	1	75	\$200.00	\$15,000.00
Fire Water Service Valves & hydrants	2	ea		SHELL	1	2	\$9,500.00	\$19,000.00
Joint Trench - Gas, Elect., CATV, Tel	150	lf		SHELL	1	150	\$250.00	\$37,500.00
Allow for utility connections	1	ls		SHELL	1	1	\$50,000.00	\$50,000.00
Storm Drain Inlets	5	ea		SHELL	1	5	\$1,500.00	\$7,500.00
Manholes	3	ea		SHELL	1	3	\$7,500.00	\$22,500.00
C3 Requirements Allowance	1	ls		SHELL	1	1	\$50,000.00	\$50,000.00
Accent Paving	1500	sf		SHELL	1	1500	\$25.00	\$37,500.00
Dust / Mud Control Measures	3	mos		SHELL	1	3	\$22,516.00	\$67,548.00
Off-Site Asphalt paving	1880	sf		SHELL	1	1880	\$7.00	\$13,160.00
On-Site Asphalt paving	6500	sf		SHELL	1	6500	\$4.00	\$26,000.00

## Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA		UOM TOTAL	\$/UNIT	TOTAL \$
				AREA	QTY			
Dewatering Allowance	1	ls		SHELL	1	1	\$50,000.00	\$50,000.00
Temporary Facilities	18	mos		SHELL	1	18	\$1,500.00	\$27,000.00
Temporary Fencing	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Temporary Water	18	mos		SHELL	1	18	\$1,000.00	\$18,000.00
Safety Equipment	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Small Tools	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Surveying	7	days		SHELL	1	7	\$2,500.00	\$17,500.00
Daily Cleanup	18	mos		SHELL	1	18	\$11,258.00	\$202,644.00
Debris Removal	18	mos		SHELL	1	18	\$6,495.00	\$116,910.00

**02900 DIVISION 2 EARTH WORK** **\$4,337,426.79**

**03300 DIVISION 3 CONCRETE**

Slab on Grade & footings - spread footing foundation	25750	sf		SHELL	1	25750	\$20.00	\$515,000.00
Elevated Podium slab	51500	sf		SHELL	1	51500	\$33.00	\$1,699,500.00
Topping slab at podium level patios	1152	sf		SHELL	1	1152	\$10.00	\$11,520.00
Concrete Garage Stairs	2	ea		SHELL	1	2	\$7,500.00	\$15,000.00
Allow for gyp-crete & acousti-mat	66675	gsf		SHELL	1	66675	\$2.40	\$160,020.00
Site Walkway Concrete	1000	sf		SHELL	1	1000	\$12.00	\$12,000.00
Lightweight concrete at elevated balconies	0	sf		SHELL	1	0	\$11.50	\$0.00
Podium Topping Slab at Common Areas	2715	sf		SHELL	1	2715	\$12.00	\$32,580.00
Lobby Entry Concrete	486	sf		SHELL	1	486	\$12.00	\$5,832.00
Planter Sub Slab - Allow	500	sf		SHELL	1	500	\$8.00	\$4,000.00
Concrete fill for metal pan stairs	0	flt		SHELL	2	0	\$2,500.00	\$0.00

**03300 DIVISION 3 CONCRETE** **\$2,455,452.00**

**04000 DIVISION 4 Masonry**

**04000 CMU**

CMU walls at utility rooms in garage - Allow	1529	sf		SHELL	1	1529	\$20.00	\$30,580.00
Pavers at podium common areas	0	sf		SHELL	1	0	\$20.00	\$0.00
Allow for false stone at exterior entry elevation	0	sf		SHELL	1	0	\$20.00	\$0.00
Pavers at lobby entries	0	sf		SHELL	1	0	\$20.00	\$0.00

# Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
<b>04000 DIVISION 4 CMU</b>									<b>\$30,580.00</b>

**05000 DIVISION 5 METAL**

**05120 structural steel**

Metal Stairs - no pan	10	flt	SHELL	1	10	\$9,000.00	\$90,000.00
Allow for Misc. Metals (Elev. Hoist beams, bollards, etc.)	1	ea	SHELL	1	1	\$25,000.00	\$25,000.00
Balcony/patio railing allowance	1680	lf	SHELL	1	1680	\$55.00	\$92,400.00
Allow for gates at parking	1	ea	SHELL	1	1	\$25,000.00	\$25,000.00
Allow for gates at trash enclosure	1	ea	SHELL	1	1	\$3,500.00	\$3,500.00
Allow for decorative metal grills at garage for vents	1	ea	SHELL	1	1	\$20,000.00	\$20,000.00

<b>05000 DIVISION 5 METAL</b>									<b>\$255,900.00</b>
-------------------------------	--	--	--	--	--	--	--	--	---------------------

**06000 DIVISION 6 WOOD & PLASTICS**

**06100 Rough Carpentry**

Wood Framing Structure	88900	gsf	SHELL	1	88900	\$22.50	\$2,000,250.00
Wood fence at adjacent properties - 6' high	0	sf	SHELL	1	0	\$9.00	\$0.00
Hardi Siding w/ exterior gypsum	37296	sf	SHELL	1	37296	\$8.00	\$298,368.00
Pergola at restaurant - allowance	0	ls	SHELL	1	0	\$25,000.00	\$0.00

<b>06100 Rough Carpentry</b>									<b>\$2,298,618.00</b>
------------------------------	--	--	--	--	--	--	--	--	-----------------------

**06200 Finish Carpentry**

Paint grade MDF no profile base at corridors	3368	lf	SHELL	1	3368	\$3.00	\$10,104.00
--	------	----	-------	---	------	--------	-------------

<b>06200 Finish Carpentry</b>									<b>\$10,104.00</b>
-------------------------------	--	--	--	--	--	--	--	--	--------------------

**06410 Cabinets & casework**

--	--	--	--	--	--	--	--

<b>06410 Cabinets &amp; casework</b>									<b>\$0.00</b>
--------------------------------------	--	--	--	--	--	--	--	--	---------------

# Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM TOTAL	\$/UNIT	TOTAL \$
<b>06000 DIVISION 6 WOOD &amp; PLASTICS</b>								<b>\$2,308,722.00</b>

**07000 DIVISION 7 ROOFING & WATERPROOFING**

**07100 Waterproofing**

Hot rubberized waterproofing at Podium & patios	3867	sf	SHELL	1	3867	\$11.50	\$44,470.50
Deck Coating at elevated Balconies	3888	sf	SHELL	1	3888	\$9.00	\$34,992.00
Vertical waterproofing at garage walls	0	sf	SHELL	1	0	\$12.50	\$0.00

<b>07100 Waterproofing</b>								<b>\$83,212.50</b>
----------------------------	--	--	--	--	--	--	--	--------------------

**07200 Insulation**

Spray K-13 on under side of podium	22225	sf	SHELL	1	22225	\$3.00	\$66,675.00
Insulation at corridor walls	30312	sf	SHELL	1	30312	\$0.40	\$12,124.80
Insulation at corridor & common area ceilings	9139	sf	SHELL	1	9139	\$0.65	\$5,940.35

<b>07200 Insulation</b>								<b>\$84,740.15</b>
-------------------------	--	--	--	--	--	--	--	--------------------

**07500 Roofing.**

Comp. Shingle Roof	0	sf	SHELL	1	0	\$7.00	\$0.00
Built Up Roofing	22225	sf	SHELL	1	22225	\$6.00	\$133,350.00

<b>07500 Roofing.</b>								<b>\$133,350.00</b>
-----------------------	--	--	--	--	--	--	--	---------------------

**07600 Sheet Metal Flashing & Trim**

Window GSM Head flashing	210	ea	SHELL	1	210	\$100.00	\$21,000.00
Patio Door flashing.	70	ea	SHELL	1	70	\$150.00	\$10,500.00
Slab/wall junction flashing	1036	lf	SHELL	1	1036	\$15.00	\$15,540.00
Cap Flashing	1036	lf	SHELL	1	1036	\$15.00	\$15,540.00
Lead Flashing @ roof penetrations	100	ea	SHELL	1	100	\$25.00	\$2,500.00
Miscellaneous flashings, gutters and downspouts.	88900	sf	SHELL	1	88900	\$1.00	\$88,900.00

<b>07600 Sheet Metal Flashing &amp; Trim</b>								<b>\$153,980.00</b>
--	--	--	--	--	--	--	--	---------------------

**07800 Expansion Joints & Firestopping**

## Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA		UOM TOTAL	\$/UNIT	TOTAL \$
				AREA	QTY			
Allow for Caulking & Sealants at exteriors and around windows	37296	sf		SHELL	1	37296	\$0.50	\$18,648.00
Allow. Caulking & sealants fire stopping at garage	3	ea		SHELL	1	3	\$5,000.00	\$15,000.00
<b>07800 Expansion Joints &amp; Firestopping</b>								<b>\$33,648.00</b>

<b>07000 DIVISION 7 ROOFING &amp; WATERPROOFING</b>	<b>\$488,930.65</b>
---	---------------------

**0800 DIVISION 8 WINDOWS & DOORS**

**08100: Windows, Steel doors, frames & hardware.**

Vinyl Window and Sliding Glass Door - Allowance	7459	sf		SHELL	1	7459	\$18.00	\$134,265.60
Balcony doors - single	70	ea		SHELL	1	70	\$900.00	\$63,000.00
Balcony doors - double	0	ea		SHELL	1	0	\$1,500.00	\$0.00
Steel doors @ stairs, lobbies & utility rooms & exits	25	ea		SHELL	1	25	\$900.00	\$22,500.00

<b>08100: Windows, Steel doors, frames &amp; hardware.</b>	<b>\$219,765.60</b>
--	---------------------

<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>	<b>\$219,765.60</b>
--	---------------------

**09000 DIVISION 9 FINISHES**

**09250 Gypsum Board Type**

Misc. Exterior Sheathing	0	gsf		SHELL	1	0	\$4.00	\$0.00
Interior non-load bearing walls framing - 20 gage	0	gsf		SHELL	1	0	\$35.00	\$0.00
MEP & utility rooms walls (including framing)	0	sf		SHELL	1	0	\$6.50	\$0.00
MEP & utility rooms ceilings (including framing)	0	sf		SHELL	1	0	\$6.50	\$0.00
Elevator shaft walls and ceiling	2200	sf		SHELL	1	2200	\$5.00	\$11,000.00
Trash chute shaft	1200	sf		SHELL	1	1200	\$5.00	\$6,000.00
Stairwells	4500	sf		SHELL	1	4500	\$6.50	\$29,250.00
Gypsum board to corridors and common area walls	30312	sf		SHELL	1	30312	\$4.00	\$121,248.00
Gypsum board to corridors and common area ceilings	9139	sf		SHELL	1	9139	\$4.00	\$36,556.00

<b>09250 Gypsum Board Type</b>	<b>\$204,054.00</b>
--------------------------------	---------------------

**09270 Plaster & Scaffold**

## Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA		UOM TOTAL	\$/UNIT	TOTAL \$
				AREA	QTY			
Allow for scaffold	37296	sf		SHELL	1	37296	\$2.00	\$74,592.00
Lath and Plaster (non acrylic integral color)	0	sf		SHELL	1	0	\$10.50	\$0.00
Float Finish at Garage Levels		sf		SHELL	1	0	\$4.00	\$0.00

**09270 Portland Cement Plaster** **\$74,592.00**

**09300 Tile**

Allow Hard flooring at lobby, rec. room, business ctr, etc.	250	sf		SHELL	1	250	\$20.00	\$5,000.00
---	-----	----	--	-------	---	-----	---------	------------

**09300 Tile** **\$5,000.00**

**09682 Carpet**

Allow for Carpet tile at office & storage	0	sy		SHELL	1	0	\$30.00	\$0.00
Rolled residential grade carpet at corridors	1015	sy		SHELL	1	1015	\$25.00	\$25,386.11

**09682 Carpet** **\$25,386.11**

**09901 Residential Painting**

Exterior Painting - trim & metals	37296	sf		SHELL	1	37296	\$1.00	\$37,296.00
Int. @ corridors & common areas	43951	sf		SHELL	1	43951	\$1.00	\$43,951.00

**09901 Residential Painting** **\$81,247.00**

**09000 DIVISION 9 FINISHES**

**\$390,279.11**

**10000 DIVISION 10 SPECIALTIES**

**10000 Specialties**

Garage signage & striping - Allow	1	ls		SHELL	1	1	\$7,500.00	\$7,500.00
Mailboxes	1	ls		SHELL	1	1	\$4,500.00	\$4,500.00
Bike Rack Allowance	0	ls		SHELL	1	0	\$5,000.00	\$0.00
Trash chutes - Allow	1	ea		SHELL	1	1	\$20,000.00	\$20,000.00

**10000 Specialties** **\$32,000.00**

**10000 DIVISION 10 SPECIALTIES**

**\$32,000.00**

# Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
<b>11000 DIVISION 11 EQUIPMENT</b>									
Garage parking lifts - Allow	0	ea		SHELL	1		0	\$20,000.00	\$0.00
									<b>\$0.00</b>
<b>11000 EQUIPMENT</b>									
									<b>\$0.00</b>
<b>11000 DIVISION 11 EQUIPMENT</b>									
									<b>\$0.00</b>
<b>12000 DIVISION 12 FURNISHINGS</b>									
<b>12510 Furnishings</b>									
Window blinds at units	7459	sf		SHELL	1		7459	\$3.00	\$22,377.60
									<b>\$22,377.60</b>
<b>12510 Furnishings</b>									
									<b>\$22,377.60</b>
<b>12000 DIVISION 12 FURNISHINGS</b>									
									<b>\$22,377.60</b>
<b>DIVISION 14 VERTICAL TRANSPORTATION</b>									
Hydraulic Elevators (Stops)	6	ea		SHELL	1		6	\$20,000.00	\$120,000.00
Smoke doors	6	ea		SHELL	1		6	\$2,500.00	\$15,000.00
Cab allowance	1	ea		SHELL	1		1	\$2,500.00	\$2,500.00
Residential lobby at 1st level finishes	1	ea		SHELL	1		1	\$5,000.00	\$5,000.00
Elevator Lobby finishes -Other than 1st floor	5	ea		SHELL	1		5	\$2,500.00	\$12,500.00
									<b>\$155,000.00</b>
<b>DIVISION 14 VERTICAL TRANSPORTATION</b>									
									<b>\$155,000.00</b>
<b>15000 DIVISION 15 MECHANICAL</b>									
<b>15300: Fire protection system</b>									
Fire protection garage level	51500	gsf		SHELL	1		51500	\$3.00	\$154,500.00
Allow for fire pump	0	ls		SHELL	1		0	\$100,000.00	\$0.00
Fire protection at rec. room, lobby	0	sf		SHELL	1		0	\$3.00	\$0.00
Fire protection Corridors & common areas	9139	sf		SHELL	1		9139	\$3.00	\$27,417.00
<b>15400: Plumbing System</b>									
Plumbing at garage	51500	gsf		SHELL	1		51500	\$3.00	\$154,500.00
Plumbing roof drains, overflows and piping	1	ls		SHELL	1		1	\$100,000.00	\$100,000.00
Plumbing at trash rooms, janitor closet etc - allow	1	ls		SHELL	1		1	\$7,500.00	\$7,500.00



## Serramonte Vista Commercial Site Residential Shell and Residential Parking

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM TOTAL	\$/UNIT	TOTAL \$
Div 14	\$155,000.00		sf	140400		\$1		
Div 15	\$548,584.00		sf	140400		\$4		
Div 16	\$227,778.00		sf	140400		\$2		
	\$11,472,795.75			140400		\$82		

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	1 Bedroom	1/1	35	800

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

**02900 DIVISION 2 LANDSCAPING**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**03300 DIVISION 3 CONCRETE**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**05000 DIVISION 5 METAL**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**06000 DIVISION 6 WOOD & PLASTICS**

**06100 Rough Carpentry**

Misc rough carpentry (backing, door box, etc..)

	0	ls	FLAT	35		0		\$600.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**06200 Finish Carpentry**

Pre-primed Pine crown molding	0	lf	FLAT	35		0		\$4.00		\$0.00
Medicine cabinets - prefinished w/mirror	1	ea	FLAT	35		35		\$100.00		\$3,500.00
Pre-primed MDF Baseboard	200	lf	FLAT	35		7001		\$2.50		\$17,503.50
Pre-primed MDF Casing - door frames ( both sides of opening)	216	lf	FLAT	35		7560		\$2.50		\$18,900.00
Shelving: Bedroom closet	8	lf	FLAT	35		267		\$8.00		\$2,133.60
Shelving: Laundry/Linen	6	lf	FLAT	35		204		\$8.00		\$1,632.40
Shelving: Foyer Closet	4	lf	FLAT	35		142		\$8.00		\$1,139.60
Allow. Misc. Millwork per residential Units	0	ls	FLAT	35		0		\$1,500.00		\$0.00

										<b>\$44,809.10</b>
--	--	--	--	--	--	--	--	--	--	--------------------

**06410 custom casework**

Cabinet package: kitchen & bathroom installed

	1	ea	FLAT	35		35		\$3,000.00		\$105,000.00
--	---	----	------	----	--	----	--	------------	--	--------------

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM TOTAL	\$/UNIT	TOTAL \$
Chinese Granite counter tops & back splash Kitchens	0		sf	FLAT	35	0	\$35.00	\$0.00
Chinese Granite counter tops & back splash at baths	0		sf	FLAT	35	0	\$35.00	\$0.00
Plastic Laminate counter tops & back splash Kitchens	37		sf	FLAT	35	1295	\$14.50	\$18,777.50
Plastic Laminate counter tops & back splash at baths	0		sf	FLAT	35	0	\$14.50	\$0.00
Cultured Marble counter tops & back splash at baths	8		sf	FLAT	35	280	\$20.00	\$5,600.00

**06410 custom casework** **\$129,377.50**

**06000 DIVISION 6 WOOD & PLASTICS** **\$174,186.60**

**07000 DIVISION 7 ROOFING & WATERPROOFING**

**07100 Waterproofing**

Shower pan	0		ea	FLAT	35	0	\$300.00	\$0.00
------------	---	--	----	------	----	---	----------	--------

**07100 Waterproofing** **\$0.00**

**07200 Insulation**

Interior and exterior wall insulation	1433		sf	FLAT	35	50170	\$0.40	\$20,068.02
Ceiling insulation	800		sf	FLAT	35	28000	\$0.65	\$18,200.00

**07200 Insulation** **\$38,268.02**

**07425: Polystyrene Foam Trim**

								\$0.00
--	--	--	--	--	--	--	--	--------

**07425: Polystyrene Foam Trim** **\$0.00**

**07500 Roofing.**

Included in shell cost								\$0.00
------------------------	--	--	--	--	--	--	--	--------

**07500 Roofing.** **\$0.00**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

<b>07600 Sheet Metal Flashing &amp; Trim</b>										
Included in shell cost										\$0.00

<b>07600 Sheet Metal Flashing &amp; Trim</b>										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

<b>07800 Expansion Joints &amp; Firestopping</b>										
Allow. Caulking & sealants fire stopping	1	ea	FLAT	35		35		\$450.00		\$15,750.00

<b>07800 Expansion Joints &amp; Firestopping</b>										<b>\$15,750.00</b>
--	--	--	--	--	--	--	--	--	--	--------------------

<b>07000 DIVISION 7 ROOFING &amp; WATERPROOFING</b>										<b>\$54,018.02</b>
---	--	--	--	--	--	--	--	--	--	--------------------

**0800 DIVISION 8 WINDOWS & DOORS**

**08100: Steel doors, frames & hardware.**

Unit entry doors, frames & hardware	1	ea	FLAT	35		35		\$750.00		\$26,250.00
Unit exterior storage doors, frames & hardware	0	ea	FLAT	35		0		\$650.00		\$0.00
Unit interior doors, frames & hardware - Single.	3	ea	FLAT	35		105		\$300.00		\$31,500.00
Unit interior doors, frames & hardware - Pocket.	0	ea	FLAT	35		0		\$350.00		\$0.00
Unit interior doors, frames & h/w - Double Sliding	1	ea	FLAT	35		35		\$350.00		\$12,250.00
Unit interior doors, frames & h/w - Double	1	ea	FLAT	35		35		\$350.00		\$12,250.00
Unit interior doors, frames & h/w - Double bi-fold	0	ea	FLAT	35		0		\$350.00		\$0.00

<b>08100: Steel doors, frames &amp; hardware.</b>										<b>\$82,250.00</b>
---	--	--	--	--	--	--	--	--	--	--------------------

**08360 Sectional Overhead Doors**

NIC										
-----	--	--	--	--	--	--	--	--	--	--

<b>08360 Sectional Overhead Doors</b>										<b>\$0.00</b>
---------------------------------------	--	--	--	--	--	--	--	--	--	---------------

**08810 Glass**

1/4" Glass shower enclosure w/ chrome	0	ea	FLAT	35		0		\$500.00		\$0.00
Mirror 1/4" polished w/clips	20	sf	FLAT	35		713		\$10.00		\$7,129.50

<b>08810 Glass</b>										<b>\$7,129.50</b>
--------------------	--	--	--	--	--	--	--	--	--	-------------------

<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>										<b>\$89,379.50</b>
--	--	--	--	--	--	--	--	--	--	--------------------

**09000 DIVISION 9 FINISHES**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	----------	-----	-------	---------	----------

**09250 Gypsum Board - Level 3 Finish**

Gypsum board to interior of exterior walls - 1 layer	315	sf	FLAT	35	11025		\$2.75	\$30,318.75
Gypsum board to interior of corridor walls - 2 layers	280	sf	FLAT	35	9800		\$2.75	\$26,950.00
Gypsum board to interior partitions - 1 layer on each side	785	sf	FLAT	35	27475		\$4.00	\$109,900.00
Gypsum board to party walls - 2 layers	500	sf	FLAT	35	17505		\$2.50	\$43,761.38
Gypsum board to interior ceilings - 2 layers	800	sf	FLAT	35	28000		\$3.00	\$84,000.00
Gypsum board to dropped soffits	200	sf	FLAT	35	7000		\$3.25	\$22,750.00
Shaft wall system at interior shafts	80	sf	FLAT	35	2800		\$3.50	\$9,800.00

**09250 Gypsum Board Type**

**\$327,480.13**

**09270 Portland Cement Plaster**

Included in shell cost

**09270 Portland Cement Plaster**

**\$0.00**

**09300 Tile**

Shower Pan	0	ea	FLAT	35	0		\$300.00	\$0.00
Cultured Marble at Guest Bath Tub / Shower surround	0	sf	FLAT	35	0		\$8.50	\$0.00
Ceramic Tile at Tub / Shower surrounds	0	sf	FLAT	35	0		\$15.00	\$0.00
Ceramic Tile at kitchen floor	0	sf	FLAT	35	0		\$15.00	\$0.00
Ceramic Tile at bathroom floor	0	sf	FLAT	35	0		\$15.00	\$0.00
Ceramic Tile at Entry	0	sf	FLAT	35	0		\$15.00	\$0.00

**09300 Tile**

**\$0.00**

**09560 Wood Strip Flooring**

Wood flooring at Kitchen & dining	0	sf	FLAT	35	0		\$15.00	\$0.00
-----------------------------------	---	----	------	----	---	--	---------	--------

**09560 Wood Strip Flooring**

**\$0.00**

**09650 Resilient Flooring**

Vinyl at Kitchen / Entry	110	sf	FLAT	35	3850		\$4.35	\$16,747.50
--------------------------	-----	----	------	----	------	--	--------	-------------

Project Name		Unit Type	Bed/Bath	# of units	SF of unit				
<b>Serramonte Vista Commercial Site</b>		<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>				
ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
Vinyl at Bathrooms	50	sf	FLAT	35	1750			\$4.35	\$7,612.50
Vinyl at Laundry	18	sf	FLAT	35	627			\$4.35	\$2,728.32
Rubber Base	0	lf	FLAT	35	0			\$1.50	\$0.00
<b>09650 Resilient Flooring</b>									<b>\$27,088.32</b>
<b>09682 Carpet</b>									
Rolled residential grade carpet - Bedrooms & halls	69	sy	FLAT	35	2415			\$25.00	\$60,375.00
<b>09682 Carpet</b>									<b>\$60,375.00</b>
<b>09701 Sound Control Matting</b>									
Allow quiet-core in bathroom and kitchen floors	0	sf	FLAT	35	0			\$2.50	\$0.00
<b>09701 Sound Control Matting</b>									<b>\$0.00</b>
<b>09901 Residential Painting</b>									
Paint Interior walls of units	3465	sf	FLAT	35	121280			\$0.70	\$84,895.69
Paint doors and jambs - Single	4	ea	FLAT	35	140			\$35.00	\$4,900.00
Paint doors and jambs - Double	2	ea	FLAT	35	70			\$45.00	\$3,150.00
Paint base board	200	lf	FLAT	35	7001			\$0.25	\$1,750.35
Paint crown	0	lf	FLAT	35	0			\$0.25	\$0.00
Paint closet shelving - allow	0	ls	FLAT	35	0			\$200.00	\$0.00
<b>09901 Residential Painting</b>									<b>\$94,696.04</b>
<b>09000 DIVISION 9 FINISHES</b>									<b>\$509,639.48</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									
<b>10820 Bath Accessories</b>									
Allow for bath accessories	1	ea	FLAT	35	35			\$150.00	\$5,250.00
<b>10820 Bath Accessories</b>									<b>\$5,250.00</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									<b>\$5,250.00</b>

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

**11000 DIVISION 11 EQUIPMENT**

**11452 Residential Appliances**

Frigidaire Freestanding Gas Range - White	1	ea	ea	FLAT	35	35		35	\$416.76	\$14,586.60
Frigidaire Dishwasher -White	1	ea	ea	FLAT	35	35		35	\$308.13	\$10,784.55
Broan Range Hood - White	1	ea	ea	FLAT	35	35		35	\$48.72	\$1,705.20
Appliance Installation	1	ea	ea	FLAT	35	35		35	\$295.00	\$10,325.00
Frigidaire - Washer/Dryer White	1	ea	ea	FLAT	35	35		35	\$975.00	\$34,125.00
Frigidaire 18CU Refer top mount - White	1	ea	ea	FLAT	35	35		35	\$535.84	\$18,754.40

**11452 Residential Appliances**

<b>11000 DIVISION 11 EQUIPMENT</b>										<b>\$90,280.75</b>
------------------------------------	--	--	--	--	--	--	--	--	--	--------------------

**12000 DIVISION 12 FURNISHINGS**

Allow for gas fireplace	0	ea	ea	FLAT	35	0		0	\$4,000.00	\$0.00
-------------------------	---	----	----	------	----	---	--	---	------------	--------

<b>12000 DIVISION 12 FURNISHINGS</b>										<b>\$0.00</b>
--------------------------------------	--	--	--	--	--	--	--	--	--	---------------

**DIVISION 14 VERTICAL TRANSPORTATION**

Included in shell cost										\$0.00
------------------------	--	--	--	--	--	--	--	--	--	--------

<b>DIVISION 14 VERTICAL TRANSPORTATION</b>										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**15000 DIVISION 15 MECHANICAL**

**15300: Fire protection system**

Fire protection system	800	sf	sf	FLAT	35	28000		28000	\$3.50	\$98,000.00
------------------------	-----	----	----	------	----	-------	--	-------	--------	-------------

**15400: Plumbing System**

Building plumbing system	5	fixt.	fixt.	FLAT	35	175		175	\$2,800.00	\$490,000.00
--------------------------	---	-------	-------	------	----	-----	--	-----	------------	--------------

**15500 Mechanical System**

Building mechanical system (Heat Only)	800	sf	sf	FLAT	35	28000		28000	\$10.00	\$280,000.00
--	-----	----	----	------	----	-------	--	-------	---------	--------------

<b>15000 DIVISION 15 MECHANICAL</b>										<b>\$868,000.00</b>
-------------------------------------	--	--	--	--	--	--	--	--	--	---------------------

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>1 Bedroom</b>	<b>1/1</b>	<b>35</b>	<b>800</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	----------	-----	-------	---------	----------

**16000 DIVISION 16 ELECTRICAL**

**16070 Electrical Residential**

Building electrical system (Power & lighting)	800		sf	FLAT	35		28000	\$12.00	\$336,000.00
Building tele/data system	800		sf	FLAT	35		28000	\$1.65	\$46,200.00

<b>16070 Electrical Residential</b>									<b>\$382,200.00</b>
-------------------------------------	--	--	--	--	--	--	--	--	---------------------

**16000 DIVISION 16 ELECTRICAL**

<b>\$382,200.00</b>
---------------------

Div 2	\$0.00	sf	28000	\$0
Div 3	\$0.00	sf	28000	\$0
Div 4		sf	28000	\$0
Div 5	\$0.00	sf	28000	\$0
Div 6	\$174,186.60	sf	28000	\$6
Div 7	\$54,018.02	sf	28000	\$2
Div 8	\$89,379.50	sf	28000	\$3
Div 9	\$509,639.48	sf	28000	\$18
Div 10	\$5,250.00	sf	28000	\$0
Div 11	\$90,280.75	sf	28000	\$3
Div 12	\$0.00	sf	28000	\$0
Div 13		sf	28000	\$0
Div 14	\$0.00	sf	28000	\$0
Div 15	\$868,000.00	sf	28000	\$31
Div 16	\$382,200.00	sf	28000	\$14

<b>Total Direct Construction Costs</b>	<b>\$2,172,954.35</b>		28000	<b>\$78</b> /sf
--	-----------------------	--	-------	-----------------

**\$62,084.41 /unit**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	2 Bedroom	2/2	31	1050

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

**02900 DIVISION 2 LANDSCAPING**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**03300 DIVISION 3 CONCRETE**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**05000 DIVISION 5 METAL**

Included in shell cost

										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

**06000 DIVISION 6 WOOD & PLASTICS**

**06100 Rough Carpentry**

Misc rough carpentry (backing, door box, etc..)

	0	ls	FLAT	31	0	\$600.00		\$0.00		<b>\$0.00</b>
--	---	----	------	----	---	----------	--	--------	--	---------------

**06200 Finish Carpentry**

Pre-primed Pine crown molding	0	lf	FLAT	31	0	\$4.00		\$0.00		
Medicine cabinets - prefinished w/mirror	2	ea	FLAT	31	62	\$100.00		\$6,200.00		
Pre-primed MDF Baseboard	287	lf	FLAT	31	8903	\$2.50		\$22,258.00		
Pre-primed MDF Casing - door frames ( both sides of opening)	306	lf	FLAT	31	9486	\$2.50		\$23,715.00		
Shelving: Bedroom closet	27	lf	FLAT	31	842	\$8.00		\$6,733.20		
Shelving: Laundry/Linen	0	lf	FLAT	31	0	\$8.00		\$0.00		
Shelving: Foyer Closet	9	lf	FLAT	31	271	\$8.00		\$2,170.00		
Allow. Misc. Millwork per residential Units	0	ls	FLAT	31	0	\$1,500.00		\$0.00		

										<b>\$61,076.20</b>
--	--	--	--	--	--	--	--	--	--	--------------------

**06410 custom casework**

Cabinet package: kitchen & bathroom installed

	1	ea	FLAT	31	31	\$3,000.00		\$93,000.00		
--	---	----	------	----	----	------------	--	-------------	--	--

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>2 Bedroom</b>	<b>2/2</b>	<b>31</b>	<b>1050</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
Chinese Granite counter tops & back splash Kitchens	0		sf	FLAT	31		0	\$35.00	\$0.00
Chinese Granite counter tops & back splash at baths	0		sf	FLAT	31		0	\$35.00	\$0.00
Plastic Laminate counter tops & back splash Kitchens	56		sf	FLAT	31		1736	\$14.50	\$25,172.00
Plastic Laminate counter tops & back splash at baths	0		sf	FLAT	31		0	\$14.50	\$0.00
Cultured Marble counter tops & back splash at baths	15		sf	FLAT	31		465	\$20.00	\$9,300.00

**06410 custom casework** **\$127,472.00**

**06000 DIVISION 6 WOOD & PLASTICS** **\$188,548.20**

**07000 DIVISION 7 ROOFING & WATERPROOFING**

**07100 Waterproofing**

Shower pan	0		ea	FLAT	31		0	\$300.00	\$0.00
------------	---	--	----	------	----	--	---	----------	--------

**07100 Waterproofing** **\$0.00**

**07200 Insulation**

Interior and exterior wall insulation	1977		sf	FLAT	31		61274	\$0.40	\$24,509.59
Ceiling insulation	1050		sf	FLAT	31		32550	\$0.65	\$21,157.50

**07200 Insulation** **\$45,667.09**

**07425: Polystyrene Foam Trim**

									\$0.00
--	--	--	--	--	--	--	--	--	--------

**07425: Polystyrene Foam Trim** **\$0.00**

**07500 Roofing.**

Included in shell cost									\$0.00
------------------------	--	--	--	--	--	--	--	--	--------

**07500 Roofing.** **\$0.00**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>2 Bedroom</b>	<b>2/2</b>	<b>31</b>	<b>1050</b>

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

<b>07600 Sheet Metal Flashing &amp; Trim</b>										
Included in shell cost										\$0.00

<b>07600 Sheet Metal Flashing &amp; Trim</b>										<b>\$0.00</b>
--	--	--	--	--	--	--	--	--	--	---------------

<b>07800 Expansion Joints &amp; Firestopping</b>										
Allow. Caulking & sealants fire stopping	1	ea	FLAT	31		31		\$450.00		\$13,950.00

<b>07800 Expansion Joints &amp; Firestopping</b>										<b>\$13,950.00</b>
--	--	--	--	--	--	--	--	--	--	--------------------

<b>07000 DIVISION 7 ROOFING &amp; WATERPROOFING</b>										<b>\$59,617.09</b>
---	--	--	--	--	--	--	--	--	--	--------------------

<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>										
--	--	--	--	--	--	--	--	--	--	--

<b>08100: Steel doors, frames &amp; hardware.</b>										
---	--	--	--	--	--	--	--	--	--	--

Unit entry doors, frames & hardware	1	ea	FLAT	31		31		\$750.00		\$23,250.00
-------------------------------------	---	----	------	----	--	----	--	----------	--	-------------

Unit exterior storage doors, frames & hardware	0	ea	FLAT	31		0		\$650.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

Unit interior doors, frames & hardware - Single.	8	ea	FLAT	31		248		\$300.00		\$74,400.00
--	---	----	------	----	--	-----	--	----------	--	-------------

Unit interior doors, frames & hardware - Pocket.	0	ea	FLAT	31		0		\$350.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

Unit interior doors, frames & h/w - Double Sliding	0	ea	FLAT	31		0		\$350.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

Unit interior doors, frames & h/w - Double	0	ea	FLAT	31		0		\$350.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

Unit interior doors, frames & h/w - Double bi-fold	0	ea	FLAT	31		0		\$350.00		\$0.00
--	---	----	------	----	--	---	--	----------	--	--------

<b>08100: Steel doors, frames &amp; hardware.</b>										<b>\$97,650.00</b>
---	--	--	--	--	--	--	--	--	--	--------------------

<b>08360 Sectional Overhead Doors</b>										
---------------------------------------	--	--	--	--	--	--	--	--	--	--

NIC										
-----	--	--	--	--	--	--	--	--	--	--

<b>08360 Sectional Overhead Doors</b>										<b>\$0.00</b>
---------------------------------------	--	--	--	--	--	--	--	--	--	---------------

<b>08810 Glass</b>										
--------------------	--	--	--	--	--	--	--	--	--	--

1/4" Glass shower enclosure w/ chrome	0	ea	FLAT	31		0		\$500.00		\$0.00
---------------------------------------	---	----	------	----	--	---	--	----------	--	--------

Mirror 1/4" polished w/clips	32	sf	FLAT	31		987		\$10.00		\$9,873.50
------------------------------	----	----	------	----	--	-----	--	---------	--	------------

<b>08810 Glass</b>										<b>\$9,873.50</b>
--------------------	--	--	--	--	--	--	--	--	--	-------------------

<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>										<b>\$107,523.50</b>
--	--	--	--	--	--	--	--	--	--	---------------------

<b>09000 DIVISION 9 FINISHES</b>										
----------------------------------	--	--	--	--	--	--	--	--	--	--

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>2 Bedroom</b>	<b>2/2</b>	<b>31</b>	<b>1050</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
<b>09250 Gypsum Board - Level 3 Finish</b>									
Gypsum board to interior of exterior walls - 1 layer	421		sf	FLAT	31		13060	\$2.75	\$35,914.97
Gypsum board to interior of corridor walls - 2 layers	357		sf	FLAT	31		11065	\$2.75	\$30,429.14
Gypsum board to interior partitions - 1 layer on each side	1205		sf	FLAT	31		37355	\$4.00	\$149,421.24
Gypsum board to party walls - 2 layers	480		sf	FLAT	31		14871	\$2.50	\$37,176.75
Gypsum board to interior ceilings - 2 layers	1050		sf	FLAT	31		32550	\$3.00	\$97,650.00
Gypsum board to dropped soffits	263		sf	FLAT	31		8138	\$3.25	\$26,446.88
Shaft wall system at interior shafts	80		sf	FLAT	31		2480	\$3.50	\$8,680.00

**09250 Gypsum Board Type** **\$385,718.97**

<b>09270 Portland Cement Plaster</b>									
Included in shell cost									

**09270 Portland Cement Plaster** **\$0.00**

<b>09300 Tile</b>									
Shower Pan	0		ea	FLAT	31		0	\$300.00	\$0.00
Cultured Marble at Guest Bath Tub / Shower surround	0		sf	FLAT	31		0	\$8.50	\$0.00
Ceramic Tile at Tub / Shower surrounds	0		sf	FLAT	31		0	\$15.00	\$0.00
Ceramic Tile at kitchen floor	0		sf	FLAT	31		0	\$15.00	\$0.00
Ceramic Tile at bathroom floor	0		sf	FLAT	31		0	\$15.00	\$0.00
Ceramic Tile at Entry	0		sf	FLAT	31		0	\$15.00	\$0.00

**09300 Tile** **\$0.00**

<b>09560 Wood Strip Flooring</b>									
Wood flooring at Kitchen & dining	0		sf	FLAT	31		0	\$15.00	\$0.00

**09560 Wood Strip Flooring** **\$0.00**

<b>09650 Resilient Flooring</b>									
Vinyl at Kitchen / Entry	162		sf	FLAT	31		5007	\$4.35	\$21,780.97

Project Name		Unit Type	Bed/Bath	# of units	SF of unit				
<b>Serramonte Vista Commercial Site</b>		<b>2 Bedroom</b>	<b>2/2</b>	<b>31</b>	<b>1050</b>				
ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
Vinyl at Bathrooms	87	sf	FLAT	31	2697		\$4.35	\$11,731.95	
Vinyl at Laundry	12	sf	FLAT	31	363		\$4.35	\$1,580.44	
Rubber Base	0	lf	FLAT	31	0		\$1.50	\$0.00	
<b>09650 Resilient Flooring</b>									<b>\$35,093.36</b>
<b>09682 Carpet</b>									
Rolled residential grade carpet - Bedrooms & halls	80	sy	FLAT	31	2474		\$25.00	\$61,860.50	
<b>09682 Carpet</b>									<b>\$61,860.50</b>
<b>09701 Sound Control Matting</b>									
Allow quiet-core in bathroom and kitchen floors	0	sf	FLAT	31	0		\$2.50	\$0.00	
<b>09701 Sound Control Matting</b>									<b>\$0.00</b>
<b>09901 Residential Painting</b>									
Paint Interior walls of units	4718	sf	FLAT	31	146256		\$0.70	\$102,379.52	
Paint doors and jambs - Single	9	ea	FLAT	31	279		\$35.00	\$9,765.00	
Paint doors and jambs - Double	0	ea	FLAT	31	0		\$45.00	\$0.00	
Paint base board	287	lf	FLAT	31	8903		\$0.25	\$2,225.80	
Paint crown	0	lf	FLAT	31	0		\$0.25	\$0.00	
Paint closet shelving - allow	0	ls	FLAT	31	0		\$200.00	\$0.00	
<b>09901 Residential Painting</b>									<b>\$114,370.32</b>
<b>09000 DIVISION 9 FINISHES</b>									<b>\$597,043.15</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									
<b>10820 Bath Accessories</b>									
Allow for bath accessories	2	ea	FLAT	31	62		\$150.00	\$9,300.00	
<b>10820 Bath Accessories</b>									<b>\$9,300.00</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									<b>\$9,300.00</b>

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	2 Bedroom	2/2	31	1050

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

**11000 DIVISION 11 EQUIPMENT**

**11452 Residential Appliances**

Frigidaire Freestanding Gas Range - White	1	ea	ea	FLAT	31	31		31	\$416.76	\$12,919.56
Frigidaire Dishwasher -White	1	ea	ea	FLAT	31	31		31	\$308.13	\$9,552.03
Broan Range Hood - White	1	ea	ea	FLAT	31	31		31	\$48.72	\$1,510.32
Appliance Installation	1	ea	ea	FLAT	31	31		31	\$295.00	\$9,145.00
Frigidaire - Washer/Dryer White	1	ea	ea	FLAT	31	31		31	\$975.00	\$30,225.00
Frigidaire 18CU Refer top mount - White	1	ea	ea	FLAT	31	31		31	\$535.84	\$16,611.04

**11452 Residential Appliances**

**11000 DIVISION 11 EQUIPMENT**

**\$79,962.95**

**12000 DIVISION 12 FURNISHINGS**

Allow for gas fireplace	0	ea	ea	FLAT	31	0		0	\$4,000.00	\$0.00
-------------------------	---	----	----	------	----	---	--	---	------------	--------

**12000 DIVISION 12 FURNISHINGS**

**\$0.00**

**DIVISION 14 VERTICAL TRANSPORTATION**

Included in shell cost										\$0.00
------------------------	--	--	--	--	--	--	--	--	--	--------

**DIVISION 14 VERTICAL TRANSPORTATION**

**\$0.00**

**15000 DIVISION 15 MECHANICAL**

**15300: Fire protection system**

Fire protection system	1050	sf	sf	FLAT	31	32550		32550	\$3.50	\$113,925.00
------------------------	------	----	----	------	----	-------	--	-------	--------	--------------

**15400: Plumbing System**

Building plumbing system	9	fixt.	fixt.	FLAT	31	279		279	\$2,800.00	\$781,200.00
--------------------------	---	-------	-------	------	----	-----	--	-----	------------	--------------

**15500 Mechanical System**

Building mechanical system (Heat Only)	1050	sf	sf	FLAT	31	32550		32550	\$10.00	\$325,500.00
--	------	----	----	------	----	-------	--	-------	---------	--------------

**15000 DIVISION 15 MECHANICAL**

**\$1,220,625.00**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	2 Bedroom	2/2	31	1050

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	----------	-----	-------	---------	----------

**16000 DIVISION 16 ELECTRICAL**

**16070 Electrical Residential**

Building electrical system (Power & lighting)	1050		sf	FLAT	31		32550	\$12.00	\$390,600.00
Building tele/data system	1050		sf	FLAT	31		32550	\$1.65	\$53,707.50

<b>16070 Electrical Residential</b>									<b>\$444,307.50</b>
-------------------------------------	--	--	--	--	--	--	--	--	---------------------

**16000 DIVISION 16 ELECTRICAL**

<b>\$444,307.50</b>
---------------------

Div 2	\$0.00	sf	32550	\$0
Div 3	\$0.00	sf	32550	\$0
Div 4		sf	32550	\$0
Div 5	\$0.00	sf	32550	\$0
Div 6	\$188,548.20	sf	32550	\$6
Div 7	\$59,617.09	sf	32550	\$2
Div 8	\$107,523.50	sf	32550	\$3
Div 9	\$597,043.15	sf	32550	\$18
Div 10	\$9,300.00	sf	32550	\$0
Div 11	\$79,962.95	sf	32550	\$2
Div 12	\$0.00	sf	32550	\$0
Div 13		sf	32550	\$0
Div 14	\$0.00	sf	32550	\$0
Div 15	\$1,220,625.00	sf	32550	\$38
Div 16	\$444,307.50	sf	32550	\$14

<b>Total Direct Construction Costs</b>	<b>\$2,706,927.39</b>		32550	<b>\$83</b> /sf
--	-----------------------	--	-------	-----------------

**\$87,320.24 /unit**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	3 Bedroom	3/2	4	1300

ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	------	-----	-----	-------	---------	----------

**02900 DIVISION 2 LANDSCAPING**

Included in shell cost

**02900 DIVISION 2 LANDSCAPING** **\$0.00**

**03300 DIVISION 3 CONCRETE**

Included in shell cost

**03300 DIVISION 3 CONCRETE** **\$0.00**

**05000 DIVISION 5 METAL**

Included in shell cost

**05000 DIVISION 5 METAL** **\$0.00**

**06000 DIVISION 6 WOOD & PLASTICS**

**06100 Rough Carpentry**

Misc rough carpentry (backing, door box, etc..)

0	ls	FLAT	4	0	\$600.00	\$0.00
---	----	------	---	---	----------	--------

**06100 Rough Carpentry** **\$0.00**

**06200 Finish Carpentry**

Pre-primed Pine crown molding	0	lf	FLAT	4	0	\$4.00	\$0.00
Medicine cabinets - prefinished w/mirror	2	ea	FLAT	4	8	\$100.00	\$800.00
Pre-primed MDF Baseboard	390	lf	FLAT	4	1560	\$2.50	\$3,900.00
Pre-primed MDF Casing - door frames ( both sides of opening)	466	lf	FLAT	4	1864	\$2.50	\$4,660.00
Shelving: Bedroom closet	30	lf	FLAT	4	120	\$8.00	\$960.00
Shelving: Laundry/Linen	20	lf	FLAT	4	80	\$8.00	\$640.00
Shelving: Foyer Closet	6	lf	FLAT	4	24	\$8.00	\$192.00
Allow. Misc. Millwork per residential Units	0	ls	FLAT	4	0	\$1,500.00	\$0.00

**06200 Finish Carpentry** **\$11,152.00**

**06410 custom casework**

Cabinet package: kitchen & bathroom installed

1	ea	FLAT	4	4	\$3,000.00	\$12,000.00
---	----	------	---	---	------------	-------------

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>3 Bedroom</b>	<b>3/2</b>	<b>4</b>	<b>1300</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM TOTAL	\$/UNIT	TOTAL \$
Chinese Granite counter tops & back splash Kitchens	0		sf	FLAT	4	0	\$35.00	\$0.00
Chinese Granite counter tops & back splash at baths	0		sf	FLAT	4	0	\$35.00	\$0.00
Plastic Laminate counter tops & back splash Kitchens	55		sf	FLAT	4	220	\$14.50	\$3,190.00
Plastic Laminate counter tops & back splash at baths	0		sf	FLAT	4	0	\$14.50	\$0.00
Cultured Marble counter tops & back splash at baths	17		sf	FLAT	4	68	\$20.00	\$1,360.00

**06410 custom casework** **\$16,550.00**

**06000 DIVISION 6 WOOD & PLASTICS** **\$27,702.00**

**07000 DIVISION 7 ROOFING & WATERPROOFING**

**07100 Waterproofing**

Shower pan	0		ea	FLAT	4	0	\$300.00	\$0.00
------------	---	--	----	------	---	---	----------	--------

**07100 Waterproofing** **\$0.00**

**07200 Insulation**

Interior and exterior wall insulation	2000		sf	FLAT	4	8000	\$0.40	\$3,200.00
---------------------------------------	------	--	----	------	---	------	--------	------------

Ceiling insulation	1300		sf	FLAT	4	5200	\$0.65	\$3,380.00
--------------------	------	--	----	------	---	------	--------	------------

**07200 Insulation** **\$6,580.00**

**07425: Polystyrene Foam Trim**

								\$0.00
--	--	--	--	--	--	--	--	--------

**07425: Polystyrene Foam Trim** **\$0.00**

**07500 Roofing.**

Included in shell cost								\$0.00
------------------------	--	--	--	--	--	--	--	--------

**07500 Roofing.** **\$0.00**

Project Name		Unit Type	Bed/Bath	# of units	SF of unit					
Serramonte Vista Commercial Site		3 Bedroom	3/2	4	1300					
ITEM	QTY	UOM	UOM	AREA	AREA	QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
<b>07600 Sheet Metal Flashing &amp; Trim</b>										
Included in shell cost										\$0.00
<b>07600 Sheet Metal Flashing &amp; Trim</b>										<b>\$0.00</b>
<b>07800 Expansion Joints &amp; Firestopping</b>										
Allow. Caulking & sealants fire stopping	1		ea	FLAT	4			4	\$450.00	\$1,800.00
<b>07800 Expansion Joints &amp; Firestopping</b>										<b>\$1,800.00</b>
<b>07000 DIVISION 7 ROOFING &amp; WATERPROOFING</b>										<b>\$8,380.00</b>
<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>										
<b>08100: Steel doors, frames &amp; hardware.</b>										
Unit entry doors, frames & hardware	1		ea	FLAT	4			4	\$750.00	\$3,000.00
Unit exterior storage doors, frames & hardware	0		ea	FLAT	4			0	\$650.00	\$0.00
Unit interior doors, frames & hardware - Single.	8		ea	FLAT	4			32	\$300.00	\$9,600.00
Unit interior doors, frames & hardware - Pocket.	0		ea	FLAT	4			0	\$350.00	\$0.00
Unit interior doors, frames & h/w - Double Sliding	2		ea	FLAT	4			8	\$350.00	\$2,800.00
Unit interior doors, frames & h/w - Double	2		ea	FLAT	4			8	\$350.00	\$2,800.00
Unit interior doors, frames & h/w - Double bi-fold	0		ea	FLAT	4			0	\$350.00	\$0.00
<b>08100: Steel doors, frames &amp; hardware.</b>										<b>\$18,200.00</b>
<b>08360 Sectional Overhead Doors</b>										
NIC										
<b>08360 Sectional Overhead Doors</b>										<b>\$0.00</b>
<b>08810 Glass</b>										
1/4" Glass shower enclosure w/ chrome	0		ea	FLAT	4			0	\$500.00	\$0.00
Mirror 1/4" polished w/clips	35		sf	FLAT	4			140	\$10.00	\$1,404.00
<b>08810 Glass</b>										<b>\$1,404.00</b>
<b>0800 DIVISION 8 WINDOWS &amp; DOORS</b>										<b>\$19,604.00</b>
<b>09000 DIVISION 9 FINISHES</b>										

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>3 Bedroom</b>	<b>3/2</b>	<b>4</b>	<b>1300</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
<b>09250 Gypsum Board - Level 3 Finish</b>									
Gypsum board to interior of exterior walls - 1 layer	931		sf	FLAT	4		3725	\$2.75	\$10,244.52
Gypsum board to interior of corridor walls - 2 layers	164		sf	FLAT	4		656	\$2.75	\$1,803.78
Gypsum board to interior partitions - 1 layer on each side	1950		sf	FLAT	4		7800	\$4.00	\$31,200.00
Gypsum board to party walls - 2 layers	500		sf	FLAT	4		2000	\$2.50	\$5,000.00
Gypsum board to interior ceilings - 2 layers	1300		sf	FLAT	4		5200	\$3.00	\$15,600.00
Gypsum board to dropped soffits	325		sf	FLAT	4		1300	\$3.25	\$4,225.00
Shaft wall system at interior shafts	80		sf	FLAT	4		320	\$3.50	\$1,120.00
									<b>\$69,193.30</b>

<b>09270 Portland Cement Plaster</b>									
Included in shell cost									
									<b>\$0.00</b>

<b>09300 Tile</b>									
Shower Pan	0		ea	FLAT	4		0	\$300.00	\$0.00
Cultured Marble at Guest Bath Tub / Shower surround	0		sf	FLAT	4		0	\$8.50	\$0.00
Ceramic Tile at Tub / Shower surrounds	0		sf	FLAT	4		0	\$15.00	\$0.00
Ceramic Tile at kitchen floor	0		sf	FLAT	4		0	\$15.00	\$0.00
Ceramic Tile at bathroom floor	0		sf	FLAT	4		0	\$15.00	\$0.00
Ceramic Tile at Entry	0		sf	FLAT	4		0	\$15.00	\$0.00
									<b>\$0.00</b>

<b>09560 Wood Strip Flooring</b>									
Wood flooring at Kitchen & dining	0		sf	FLAT	4		0	\$15.00	\$0.00
									<b>\$0.00</b>

<b>09650 Resilient Flooring</b>									
Vinyl at Kitchen / Entry	185		sf	FLAT	4		740	\$4.35	\$3,219.00

Project Name		Unit Type	Bed/Bath	# of units	SF of unit				
<b>Serramonte Vista Commercial Site</b>		<b>3 Bedroom</b>	<b>3/2</b>	<b>4</b>	<b>1300</b>				
ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
Vinyl at Bathrooms	90	sf	FLAT	4	360		\$4.35	\$1,566.00	
Vinyl at Laundry	12	sf	FLAT	4	48		\$4.35	\$208.80	
Rubber Base	0	lf	FLAT	4	0		\$1.50	\$0.00	
<b>09650 Resilient Flooring</b>									<b>\$4,993.80</b>
<b>09682 Carpet</b>									
Rolled residential grade carpet - Bedrooms & halls	113	sy	FLAT	4	450		\$25.00	\$11,255.56	
<b>09682 Carpet</b>									<b>\$11,255.56</b>
<b>09701 Sound Control Matting</b>									
Allow quiet-core in bathroom and kitchen floors	0	sf	FLAT	4	0		\$2.50	\$0.00	
<b>09701 Sound Control Matting</b>									<b>\$0.00</b>
<b>09901 Residential Painting</b>									
Paint Interior walls of units	6795	sf	FLAT	4	27181		\$0.70	\$19,026.84	
Paint doors and jambs - Single	9	ea	FLAT	4	36		\$35.00	\$1,260.00	
Paint doors and jambs - Double	4	ea	FLAT	4	16		\$45.00	\$720.00	
Paint base board	390	lf	FLAT	4	1560		\$0.25	\$390.00	
Paint crown	0	lf	FLAT	4	0		\$0.25	\$0.00	
Paint closet shelving - allow	0	ls	FLAT	4	0		\$200.00	\$0.00	
<b>09901 Residential Painting</b>									<b>\$21,396.84</b>
<b>09000 DIVISION 9 FINISHES</b>									<b>\$106,839.50</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									
<b>10820 Bath Accessories</b>									
Allow for bath accessories	2	ea	FLAT	4	8		\$150.00	\$1,200.00	
<b>10820 Bath Accessories</b>									<b>\$1,200.00</b>
<b>10000 DIVISION 10 SPECIALTIES</b>									<b>\$1,200.00</b>

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
<b>Serramonte Vista Commercial Site</b>	<b>3 Bedroom</b>	<b>3/2</b>	<b>4</b>	<b>1300</b>

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	----------	-----	-------	---------	----------

**11000 DIVISION 11 EQUIPMENT**

**11452 Residential Appliances**

Frigidaire Freestanding Gas Range - White	1	ea	FLAT	4	4		\$416.76	\$1,667.04
Frigidaire Dishwasher -White	1	ea	FLAT	4	4		\$308.13	\$1,232.52
Broan Range Hood - White	1	ea	FLAT	4	4		\$48.72	\$194.88
Appliance Installation	1	ea	FLAT	4	4		\$295.00	\$1,180.00
Frigidaire - Washer/Dryer White	1	ea	FLAT	4	4		\$975.00	\$3,900.00
Frigidaire 18CU Refer top mount - White	1	ea	FLAT	4	4		\$535.84	\$2,143.36

**11452 Residential Appliances**

**11000 DIVISION 11 EQUIPMENT**

**\$10,317.80**

**12000 DIVISION 12 FURNISHINGS**

Allow for gas fireplace	0	ea	FLAT	4	0		\$4,000.00	\$0.00
-------------------------	---	----	------	---	---	--	------------	--------

**12000 DIVISION 12 FURNISHINGS**

**\$0.00**

**DIVISION 14 VERTICAL TRANSPORTATION**

Included in shell cost								\$0.00
------------------------	--	--	--	--	--	--	--	--------

**DIVISION 14 VERTICAL TRANSPORTATION**

**\$0.00**

**15000 DIVISION 15 MECHANICAL**

**15300: Fire protection system**

Fire protection system	1300	sf	FLAT	4	5200		\$3.50	\$18,200.00
------------------------	------	----	------	---	------	--	--------	-------------

**15400: Plumbing System**

Building plumbing system	9	fixt.	FLAT	4	36		\$2,800.00	\$100,800.00
--------------------------	---	-------	------	---	----	--	------------	--------------

**15500 Mechanical System**

Building mechanical system (Heat Only)	1300	sf	FLAT	4	5200		\$10.00	\$52,000.00
--	------	----	------	---	------	--	---------	-------------

**15000 DIVISION 15 MECHANICAL**

**\$171,000.00**

Project Name	Unit Type	Bed/Bath	# of units	SF of unit
Serramonte Vista Commercial Site	3 Bedroom	3/2	4	1300

ITEM	QTY	UOM	UOM	AREA	AREA QTY	UOM	TOTAL	\$/UNIT	TOTAL \$
------	-----	-----	-----	------	----------	-----	-------	---------	----------

**16000 DIVISION 16 ELECTRICAL**

**16070 Electrical Residential**

Building electrical system (Power & lighting)	1300		sf	FLAT	4		5200	\$12.00	\$62,400.00
Building tele/data system	1300		sf	FLAT	4		5200	\$1.65	\$8,580.00

<b>16070 Electrical Residential</b>									<b>\$70,980.00</b>
-------------------------------------	--	--	--	--	--	--	--	--	--------------------

**16000 DIVISION 16 ELECTRICAL**

<b>\$70,980.00</b>
--------------------

Div 2	\$0.00	sf	5200	\$0
Div 3	\$0.00	sf	5200	\$0
Div 4		sf	5200	\$0
Div 5	\$0.00	sf	5200	\$0
Div 6	\$27,702.00	sf	5200	\$5
Div 7	\$8,380.00	sf	5200	\$2
Div 8	\$19,604.00	sf	5200	\$4
Div 9	\$106,839.50	sf	5200	\$21
Div 10	\$1,200.00	sf	5200	\$0
Div 11	\$10,317.80	sf	5200	\$2
Div 12	\$0.00	sf	5200	\$0
Div 13		sf	5200	\$0
Div 14	\$0.00	sf	5200	\$0
Div 15	\$171,000.00	sf	5200	\$33
Div 16	\$70,980.00	sf	5200	\$14
<b>Total Direct Construction Costs</b>	<b>\$416,023.30</b>		5200	<b>\$80</b> /sf

**\$104,005.82 /unit**